



# PACIFIC TRANSGLOBAL CONSTRUCTION CORP.

---

---

61 Southside Avenue, Bldg. B  
Hastings on Hudson, NY 10706  
Office: 914.423.0814  
Fax: 914.963.6116  
www.pacifictransglobal.com

License Nos.  
WC-15276-H04  
Yonkers 017  
CT HIC0626061  
NYC Tracking #606935

## Addendum

Customer: Village of Hastings  
7 Maple Avenue  
Hastings on Hudson, NY 10706

Contact: Charles Minozzi, Jr.  
Building Inspector  
914.478.3400 xt613  
cminozzi@hastingsgov.org

Project Location: Municipal Building  
7 Maple Avenue  
Hastings on Hudson, NY 10706

Scope of Project: Added scope to Entrance Column Project - Replace structural columns behind decorative covers – New Beams as per site visit and Steven Costa, P.E., Proposed Column CD, dated 7/8/16

Date of Proposal: August 4, 2016

### Work to be performed:

- Fabricate six steel structural columns, W6x15 with ½” steel plates, welded top and bottom. Plates and beam will be pre-drilled at attachment points and for wood cladding.
- Fabricate lower base plate with solid pins for attachment to existing cast iron base
- Paint steel for rust-proofing, two coats Super Spec DTM
- Provide temporary support for building overhang as needed
- Remove and dispose of existing structural column, 2x10
- Install base plate and secure as per detail
- Install wood blocking between existing 2x10 to remain
- Rig new steel column in place, secure tops with ¾” Spax lag bolts , level and adjust height with jack screws
- Install temporary shim and base angle clips
- *Note: Work column by column until all six units are installed*
- Re-adjust columns and jack screws as needed to confirm that all units are carrying load properly
- Allow time for A.E inspections as needed
- Re-shim base plates after final adjustments
- Final welding of angle clips to permanently affix column to lower base plates
- Clean and rust proof paint all welds
- Dry pack grout between upper and lower base plates
- Clad two sides of new columns with PT 2x8 – bolt with ¾”galvanized carriage bolts
- Remove and dispose of all debris

The above-detailed scope of work will be completed in accordance with customer specifications, using, where applicable, customer’s desired materials within budget. All necessary materials will be provided by PacificTransglobal Construction Corp. Pacific Transglobal Construction Corp. will be responsible for and will perform daily clean-up and removal of debris.

*We hereby propose to furnish materials and labor for the above-detailed project for the sum of \$31,400.00  
All work budgeted for weekday, dayshift – non-union, no prevailing wage*

---

Payment of one-third of the amount above is due prior to commencement of work, with the balance to be paid upon completion of work. Payment terms may be re-negotiated as per customer's standard payment practices.

Cost of the work as set forth above is exclusive of applicable taxes and 1.5% interest, compounded annually, payable upon any amount of payment in default by the customer.

Any modifications or deviations to the above-detailed scope of work may result in additional fees. All such fees will be approved by management prior to incurring such fees and will be invoiced appropriately.

This proposal will remain valid for 30 days from the date hereof.

Please sign and date below to indicate acceptance of this proposal.

We look forward to working with you. Please do not hesitate to contact us with any questions regarding this proposal.

**\*\*Acceptance of Proposal\*\***

We hereby accept the terms of this proposal as detailed above. Pacific Transglobal Construction Corp. is hereby authorized to perform the work as specified.

Agreed and Accepted By:

By: \_\_\_\_\_

Print Name: \_\_\_\_\_

Title: \_\_\_\_\_

Dated: \_\_\_\_\_