



## VILLAGE OF HASTINGS-ON-HUDSON

Municipal Building  
7 Maple Avenue  
Hastings-on-Hudson, New York 10706  
Mary Beth Murphy, Village Manager  
[villagemanager@Hastingsgov.org](mailto:villagemanager@Hastingsgov.org)  
914 478 3420

### **Request for Bids – Hillside Woods & Park Deer Exclosure Fencing Hastings-on-Hudson**

**Addendum No. 1  
January 26, 2023**

#### **Walkthrough List, Questions & Answers, Updated Proposal Form, & Addendum Acknowledgement**

This addendum will contain the walkthrough list (attached), answers to questions raised at the walkthrough and received via email, an updated proposal form, and the addendum acknowledgement.

#### **Addendum Acknowledgement**

Bidder acknowledges receipt of Addendum as follows:

---

Signature

#### **Questions & Answers**

1. Will the existing fence remain?
  - a. The existing fence will remain in place.
2. Will the Village accept alternate proposals to maintain an 8' perimeter around the fence?
  - a. The Village will accept alternate proposals to maintain a 3'-4' perimeter on either side of the fence.
3. What do the white-marked trees indicate?
  - a. The white-marked trees indicate suspected invasive tree species that will need to be cleared as part of the overall woods restoration. For this project, any tree within the path or the maintenance perimeter of the fence will come down.
4. Will the Village stake out the perimeter/corners of the site?
  - a. The Village will stake out the perimeter/corners of the site. The perimeter can be confirmed at the first construction meeting.
5. Will the Village accept air driving posts into the soil?
  - a. The Village will not accept air driving posts into the soil.
6. What is the vertical and horizontal spacing for the fence?
  - a. The field farm and game fence as identified has a decreasing horizontal spacing. The vertical spacing can be either 6" or 12". The Village does not have a preference.
7. Will there be a staging area?
  - a. The Village will allow staging on-street at Edgewood Avenue and Overlook Road, a possible staging area at Children's Village, as well as the final placement of the access gate will be confirmed prior to the start of construction. Short-term,

temporary storage at the Hillside Elementary School will be discussed with the school district and will be confirmed prior to the start of construction.

8. What should be done with the trees cut down to install the fence?
  - a. Cut trees can be left in the woods, removed from the trail and fence line.
9. What is the anticipated timeline?
  - a. The bid specifications identified work beginning within thirty days of Contractor receiving the Letter of Award/Notice to Proceed, with a 90 calendar day completion timeline. The Village anticipates that this work begins in the spring of 2023 and is completed within the summer of 2023.
10. How deep do the core drills have to be?
  - a. Each fence post must be secured in the ground to a depth of 36" in soil. If securing the fence post into rock, a core drill depth of 12" must be secured.
11. Base bid 5000 LF -How many core drills in rock?
  - a. The Village has estimated a total number of 250 core drills for this project. The Village will also request a line item for additional core drills as needed.
12. What is the acceptable gap on the bottom of the fence?
  - a. A gap of 6" to 12" is acceptable at the bottom of the fence.
13. Is a bid bond required?
  - a. No bid bond is required for this project.

**BID PROPOSAL**  
**PROPOSED INSTALLATION OF DEER EXCLOSURE FENCING IN HILLSIDE WOODS**  
**HASTINGS-ON-HUDSON, NY**

Name of Bidder \_\_\_\_\_  
 Address \_\_\_\_\_  
 City, State Zip \_\_\_\_\_

Email: \_\_\_\_\_  
 Telephone: \_\_\_\_\_  
 Fax: \_\_\_\_\_

BID	UNIT	EST. QUANT.	UNIT PRICE	UNIT PRICE	TOTAL PRICE
			(IN NUMBERS)	(IN WORDS)	
8 FEET HIGH 12 GAUGE GALVANIZED WIRE, POSTS, HARDWARE, CAPS, CONCRETE FOOTINGS	LF	5000			
ALTERNATE 8 FEET HIGH 12 GAUGE GALVANIZED WIRE, POSTS, HARDWARE, CAPS, CONCRETE FOOTINGS	LF	7000			
“S” GATE FOR PEDESTRIAN ACCESS	EA	6			
DOUBLE PANEL GATE FOR VEHICLE ACCESS (COMMERCIAL GRADE)	EA	3			
CORE DRILL IN ROCK	EA	250			
GALVANIZED WIRE 9 GAUGE TOP AND BOTTOM	LF	10000			
ALTERNATE GALVANIZED WIRE 9 GAUGE TOP AND BOTTOM	LF	14000			
RESTORATION/CORRECTIVE MEASURES	NP	NP	NP	NON-PAYMENT	0.00

**Base bid:** 5,000 LF of Field farm and game fence, galvanized 20-96, fixed knot 12-gauge galvanized wire (or equivalent), posts, hardware, caps, concrete footings, core drilling in rock, galvanized wire 9-gauge top and bottom.

---

**Alternate bid:** 7,000 LF of Field farm and game fence, galvanized 20-96, fixed knot 12-gauge galvanized wire (or equivalent), posts, hardware, caps, concrete footings, core drilling in rock, galvanized wire 9-gauge top and bottom.

---

**Line Item:** Cost per additional core drill in rock above estimated 250. \_\_\_\_\_

**Line Item:** Cost per additional fence terminal. \_\_\_\_\_

The total bid shall be the sum of the extensions (unit price multiplied by estimated quantity, for each item). It is stated here only as a convenience for comparison of bids. If there are any errors in addition or multiplication, the unit prices for each item shall govern, and the bid comparison will be made on the basis of correct arithmetic applied to these unit prices. In case of a discrepancy between the unit price in words and the unit price in numbers, the unit prices in words shall govern.

The estimated quantities are not guaranteed and are only for bid comparison purposes and final payment will be made for actual quantities regardless of the estimated quantities contained herein.

The contractor is further advised that the estimated quantities shown in the Bid Sheets may be reduced or deleted in order to ensure that this Contract can be completed within the budget established for this work. In the event that certain work is deleted or reduced, the Unit Price Bid shall remain in effect for this work.

**Hillside Woods & Park Deer Enclosure Fencing Walkthrough  
January 17, 2023**

**PLEASE PRINT CLEARLY**

Name	Company	Phone	Email
Mary Beth Murphy, Village Manager	Hastings-on-Hudson	914-478-3420	<a href="mailto:VillageManager@hastingsgov.org">VillageManager@hastingsgov.org</a>
Aaron Podhurst, Superintendent & Parks and Recreation	Hastings-on-Hudson	914-478-2380 x 640	<a href="mailto:APodhurst@hastingsgov.org">APodhurst@hastingsgov.org</a>
Anthony Costantini, Village Clerk	Hastings-on-Hudson	914-478-3457	<a href="mailto:ACostantini@hastingsgov.org">ACostantini@hastingsgov.org</a>
RAFAEL TAVAREZ	Fox Fence	973-779-9592	FxFence417@aol.com
Matt New Flynn	Moy Construction	914-320-4714	moycorpmf@aol.com
Tyler Bantrewick	D. F. Eastwood Construction	516 442 0012	bids@allislandfence.com
Joseph Tomanelli	Capital fence & <sup>Construction</sup> Company	914 572 4339	Rob@CapitalfenceNY.com
ROBERT WALTER	Northern Fence Co	914 248 1100	Rob@NorthernFenceS.com
Kenny Lewis	JK Fence	914-382-5810	JK Fence 82@aol.com
John Koller	Yaboo Fence	845 358 0118	johnk@yaboo fence.com
MATT Gedeiko	YABOO Fence Co	" "	mattjr@yaboo fence.com
Doug Hale	BASH COAT	(814)-577-8729	dhalebashcontracting@verizon.net
SAL CHIAPPETTA	CENTRAL WD. INC.	(914) 793-4700	salcentral@yahoo.com